SANITARY DIVISION.

Dated 27th April 1910.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Sanitary Division, up to 12 noon of 2nd May 1910 for laying out New Extension between Chamrajpet and Basavangudi Extensions. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1910.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's office at Bangalore between the hours of 12 and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for laying out New Extension between Chamrajpet and Basavangudi Extensions," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Sanitary Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement of quantities to be worked out for laying out New Extension between Chamarajpet and Basavangudi Extensions.

No.	Items	Per	Quantity
	Laying out roads.		
1	Earthwork, excavation	C. yd.	251
2	Do embankment including lead	„	11,344
3	Forming road	S. yd.	13,432
4	Side drains both sides	100 R. ft.	3,967
5	Collection of gravel	C. yd.	1,609
6	Consolidation of gravel	„	1,609
7	Collecting and spreading sand	„	23
8	Jungle clearing	S. yd.	10,800
9	Turfing	Sqr.	„
10	Rock blasting	C. yd.	22
11	Cleaning side drains both sides	R. ft.	9,630
12	Revetment to support sides of drains	C. yd.	1,288
	Constructing tunnels.		
13	Excavation	C. yd.	379
14	Burnt stone in chunam	C. ft.	5,474
15	Burnt stone slabs 6" thick	S. ft.	1,211
16	Do 4" dressed	„	551
17	Cap over pedestals	Each	4
18	Pointing with chunam	Sqr.	30·30
19	Guard stones	Each	36
20	Burnt dry stone work	C. yd.	29
	Constructing main drain.		
21	Earthwork, excavation	C. yd.	749
22	Rock blasting	„	89
23	Old stone in chunam including dismantling	C. ft.	5,400
24	New stone in chunam	„	16,200
25	Dry stone work	C. yd.	440
26	Pointing with chunam	Sqr.	144
27	Earthwork, filling including carting	C. yd.	1,320

J. BHORE,
Sanitary Engineer.